

Full Service Center 827 7th Street, Room 102 Sacramento, CA 95814 <i>M-F 8:30am - 4:30pm</i>	East Area Service Center 5229 Hazel Avenue, Suite B Fair Oaks, CA 95628 <i>M-Tu. 9:00am - 4:00pm</i>
Bradshaw Center 9700 Goethe Road, Suite A Sacramento, CA 95827 <i>M-F 8:30am - 4:30pm</i>	North Area Service Center 3331 Peacekeeper Wy., Suite 100 McClellan, CA 95652 <i>W-Th. 9:00am - 4:00pm</i>

This REQUIRED INSPECTIONS Label is intended as a guide and may not include all the required inspections for your specific permit.

Inspections 875-5381

This entire section applies for this permit

Required Inspections
Gunite Swimming Pool and/or Spa

1. Combination pre-gunite #501
 - Location: set-backs; utility easements.
 - Structural: rebar, soil, clearances.
 - Plumbing: filled w/ 35#, gas pipe test, reroute sewer or water lines w/ test.
 - Electrical: clearance to overhead lines, bonding of steel & forming shell, conduit to equipment, bond metal object within 5 ft.
 - Safety: provide gate requirements to owner.
 - Electrical: Overhead clearances, grounding & bonding, main panel, switch & plug locations, time clock, wire & breaker sizing, GFCI, light has low water cutoff, GFCI plugs, pool/spa lights.
 - Minimum Floor Requirements
2. Combination pre-deck #502
 - Final bonding of diving board, grab rails, slides, disabled access inserts and/or rope ties. Bonding grip may be required.
 - Add common bonding grid under paved walking surface.
3. Combination pre-plaster #503
 - Fence: 5' high, sc gates, swing outward.
 - Alarms: Meet UL 2017 Standard.
 - Electrical: potting in shell, GFCI installed, light niche cord long enough.
4. Combination Pool Final #599
 - Structural/ Safety: sidewalks, grading, equip. location, general appearance, solar, required barriers.
 - Plumbing: exposed piping leaks, APA gas value, T&P for heater (if required); secured equip., pool cover, painted PVC.
5. _____

[Ø] Does not apply for this section
 3 digit inspection codes preceded by #